

5T Cable Drum Jack Test Result

Test Summary-PASS

- Product: Cable drum jack- C.10.CJ.5T
- Inspection date: 20 April, 2020
- Inspection equipment: 5T vertical hydraulic tensile strength tester
- Inspection type: Tensile test
- Testing organization: Fibertel
- Testing officer: Dapeng He
- Testing supervisor: Wei Ma
- Test authenticator: Sai Lee
- Inspection standard: DL/T875 2004 power transmission tools and machine for overhead line construction design, test basic requirement

Test Result

- Under rated load of 50KN for 30 minutes, tested item fits inspection standards
- In the overload test of 75KN for 30 minutes, tested item is intact and fits inspection standards
- Product meets specified standards



**Specifications are subject to change without notice based on technical recommendations and related product enhancements*

10T Cable Drum Jack Test Result

Test Summary-PASS

- Product: Cable drum jack- C.10.CJ.10T
- Inspection date: 20 April, 2020
- Inspection equipment: 10T vertical hydraulic tensile strength tester
- Inspection type: Tensile test
- Testing organization: Fibertel
- Testing officer: Dapeng He
- Testing supervisor: Wei Ma
- Test authenticator: Sai Lee
- Inspection standard: DL/T875 2004 power transmission tools and machine for overhead line construction design, test basic requirement

Test Result

- Under rated load of 100KN for 30 minutes, tested item fits inspection standards
- In the overload test of 150KN for 30 minutes, tested item is intact and fits inspection standards
- Product meets specified standards



**Specifications are subject to change without notice based on technical recommendations and related product enhancements*